

①

NOTE: WELL NAME ON RBDMs
HAS NAME AS HOLZHAUSER
SOUTH #410

4-070166

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-21,594-0000

SE SW NE /4 SEC. 26, 09 S, 22 W
2970 feet from S section line
1650 feet from E section line

3/15

Holzhauser South #124.48
Lease: Ironclad Well # 410

Operator license# 4952

County: Graham

Operator: Starr F. Schlobohm Oil

Well total depth 3830 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 177 feet
W/140 sxs.

Address: 47 Michawanic Rd #3D
Ossipee, NH 03864-3787

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Starr F. Schlobohm Oil Operations License# 4952

Address: 47 Michawanic Rd #3D - Ossipee, NH. 03864-3787

Company to plug at: Hour: 10:00 A.M. Day: 15 Month: March Year: 2000

Plugging proposal received from: _____

Company: Starr F. Schlobohm Oil Operations Phone: 603-522-9760

Were: 5 1/2" casing set at 3828' w/150 sxs - 8% Salt - 4% Gilsonite.
Perforations at 3570' - 3784'. Bad casing at 1270' - 1327' - 1510' - 1732'.
Dakota at 820' - 1120'. Anhy at 1858' - 1895'.
Emergency plug orders given while pulling unit over hole.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:30 P.M. Day: 15, Month: March, Year: 2000

Actual plugging report: Ran 2 3/8" tubing to 3100'. Allied pumped 75 sxs with 300# hulls.
Pulled tubing to 2000' and pumped 75 sxs with 300# hulls. Pulled to 900' and pumped 65 sxs
with 200# hulls. Cement circulated. PTOH. Squeezed 45 sxs with 200# S.I.P.
Hooked up to backside and pressured to 500#.

RECEIVED
STATE CORPORATION COMMISSION
3/20/00
MAR 20 2000

Remarks: Backside squeezed 4-7-82 with 400 sxs 50/50 pozmix and 6% gel.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2370 GL

CONSERVATION DIVISION
Wichita, Kansas

Richard Williams
(agent)

I did / did not observe the plugging.

INVOICED
DATE 4/3/00
INV. NO. 061498

Form CP-2/3

②