

12-18-87

5-21-67

6 020432

API NUMBER 15- 065-20041-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330' N and 330' E, SEC. 26, T 9, S, R 22 W/4E
Ctr.

2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Lease Name Ironclad Unit Well # 8

Operator: B J Oil Co.
Name & Address: 2911 Canterbury
Hays, Ks. 67601

County Graham 124.12
Well Total Depth 3819 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 249 w/200 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Oil Co. License Number 5465

Address Same

Company to plug at: Hour 9:00 Day: 18 Month: Dec. Year: 19 87

Plugging proposal received from Vernon Chard

(company name) B. J. (phone) _____

Order 200 lbs 50/50 Poz 6% Gel 3% Cal Cl 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss. 200 sks Econlite and Hulls.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour 3:30 PM Day: 18 Month: Dec. Year: 19 87

ACTUAL PLUGGING REPORT 4 1/2 set at 3819' w/175 sks

Perfs 3629' to 3578'

2-stage DV tool at 1872' w/500 sks circ.

12/29/87

Pump down 4 1/2 20 sks Econolite

" " 140 sks cement w/Hulls.

Max pressure 500 lbs shut in 300 lbs.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

Cemented by Allied.

DATE 1-6-88

INV. NO. 19351

Signed Gilbert Balthazor (TECHNICIAN)