

15-065-00903-00-01

031456

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1962

SE SE NW SEC. 27, T 9 S, R 22 W/Ex
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30160

Lease Name Moore Well # 1

Operator: Clute Oil Corp

County Graham 130.71

Name & Address 444 17th St. Suite 608

Well Total Depth 4022 feet

Denver, Colorado 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor C and L Well Service License Number

Address Plainville, Ks.

Company to plug at: Hour: PM Day: 27 Month: Nov Year: 19 90

Plugging proposal received from Bob Plant

(company name) Clute Oil and H and C (phone)

were: 8 5/8 set at 238 w/170 sks. 5 1/2 set at 3990 w/150 sks.

PBTD 3960. Perfs 3654 - 3922. RBP at 3500. Packer set at 3160 w/150 sks cement below packer

Order 350 sks 65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co. Plant water trucks.

C and L Rig on hole.

Perf shots at 1885. Holes in tubing 1154 - 1214.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 PM Day: 27 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1970 circ cmt to surface w/170 sks cement

blend tied onto 5 1/2 and sq to max psi 400 lbs. Close in psi 400 lbs. Locked up. Sq 8 5/8 w/150 sks cement blend w/200 lbs. hulls mixed into max psi 150 lbs. Close in psi 150 lbs.

Plug complete

12/28/90

Wichita, Kansas

Remarks:

INVOICED If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-4-91

INV. NO. 30317

11-27

Carl S.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow