

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03009-00-00
Spot: CNWNWSW Sec/Twnshp/Rge: 31-9S-22W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: SUTOR E Well Number: 1
County: GRAHAM Total Vertical Depth: 4075 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 235
Production: Size 4.5 feet: 3932
Liner: Size feet:

\$ 132.44

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 4:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/17/2001 6:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 235' cwc. 4 1/2" set at 3932'.
Cement at surface in 8 5/8" annulus - squeezes N/A.
Could not pull pipe.
Fluid Level near 3000'.
Loaded hole with 8 yards Redi-Mix - 10 yards by yield.
Prod. Perf 3736' - 3740'.
Plug complete.

INVOICED

DATE 5-01-01
WV. NO. 2001061742

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 1 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #6-1.

Plugged through: CSG

District: 04

ND

Signed

Carl Goodrow

(TECHNICIAN)

PETROLEUM, INC

#1 SUTOR 'E'

31-9-22W

NW NW SW

Contr. GARVEY DRIG CO

GRAHAM County

E 2378 RB

Comm. 8-24-57

Comp. 11-15-57

IP

170 BOPD/LANS

PHY POT

Tops	Depth	Datum
ANH	1960	418
HEEB	3607	-1229
TOR	3629	-1251
LANS	3643	-1265
B/KC	3872	-1494
TD	4075	-1697

Casing
 8" 235
 4" 3932
 DST 3638-3740/1 HR, 360' M, BHP 1100#
 DST 3738-3810/1 HR, G/30", 3480' GSY 0, 0#
 DST 3792-3810/15", 1320' GIP, 2130' GSY 0,
 BHP 1140#
 DST 3809-50/1 HR, G/30", 3000' GSY 0, BHP
 1020#: DST 3830-50/1 HR, 31' SL OCM, 0#
 DST 3849-75/1 HR, 10' MUD, BHP 0#
 CO 3895: 24/3824-30: TST 1 BOPH, NATL: ACID
 2500: SWB 20 BOPH, NW: PLUG 3813: 24/3806-
 12: TST 30 BOPH, NW, NATL: ACID 2500: SWB
 21 BOPH, NW: PLUG 3790: 16/3736-40: 12 GW
 VESPER POOL & 1 GOPH: ACID 250:
 3 1/2 BFPH, 95% WTR: SQZ:
 PERF 3736-40

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS