

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03005-00-00
Spot: CW2NWSE Sec/Twnshp/Rge: 31-9S-22W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SUTOR Well Number: 5
County: GRAHAM Total Vertical Depth: 3893 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 259 ^{263 LK} ^{ZAP}
Production: Size 5.5 feet: 3789
Liner: Size feet: 3126.52

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/19/2001 8:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/19/2001 9:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 250' cwc. 5 1/2" set at 3789'.
Prod Perfs 3764' - 3795'.
Cement at surface in braden head - two stage N/A.
Fluid Level near 3000'.
Loaded 5 1/2" with 8 yards Redi-Mix - 10 yards by yield.
Plug complete.

INVOICED
DATE 5-01-01
WV. NO. 2001061742

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 1 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #3-5.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)


APR 24 2001

K & E DRILLING #5 SUTOR 31-9-22W
 W2 NW SE
 Contr. K & E DRLG GRAHAM County
 E 2361 RB Comm. 1-8-58 Comp. 2-14-58 IP 90 BOPD

Tops	Depth	Datum
ANH	1920	441
HEEB	3596	-1235
TOR	3618	-1257
LANS	3632	-1271
R/KC	3851	-1490
TD	3893	-1532

Casing
 5" 3789
 DST 3750-95/1½ HR, 180' SL OCM
 240' VH OCM, BHP 935#
 DST 3795-3815/30", 12' MUD,
 BHP 35#
 PERF 16/3764-68; 24/3789-95
 ACID 2000: SWB 5½ BOPH/5 HR

VESPER POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS