

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03010-00-00
Spot: CE2NWSW Sec/Twnshp/Rge: 31-9S-22W
1980 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: SUTOR E Well Number: 2
County: GRAHAM Total Vertical Depth: 3925 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 247
Production: Size 4.5 feet: 3922
Liner: Size feet:

\$127.56

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 12:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/17/2001 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 247' cwc. 4 1/2" set at 3922'.
Cement in braden head - could not pull casing - squeezes N/A.
Fluid Level near 3000'.
Loaded 4 1/2" casing with 8 yards Redi-Mix -10 yards by yield.
Prod. Perfs 3812' - 3830'.
Plug complete.

INVOICED
DATE 5-01-01
INV. NO. 2001061742

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 1 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #6-2.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

PETROLEUM, INC

#2

SUTOR 'E'

31-9-22W

E2 NW SW

Contr. GARVEY DRLG

GRAHAM

County

E 2383RB Comm. 9-25-57 Comp. 11-29-57 IP 90 BOPD

NW

Tops	Depth	Datum
ANH	1940	443
TOP	3392	-1009
HEEB	3613	-1230
TOR	3635	-1252
LANS	3649	-1266
B/KC	3877	-1494
TD	3925	-1542

Casing

8" 247

4" 3922

DST 3650-3745/1 HR, 470' WTRY MUD, BHP

1100#

DST 3763-95/1 HR, 30' MUD, BHP 200#

DST 3805-15/1 HR, G/45", 2160' FR O, BHP

1120#

DST 3820-35/1 HR, G/17", 3505' FR OIL, BHP

1190#

DST 3844-3925/1/2 HR, 35' MUD, BHP 300#

VESPER POOL CO 3899: PERF 24/3824-30

16/3812-16: SWB 22 BOPH/
4 HRS, NW: ACID 5000

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS