

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03011-00-00
Spot: CW2NESW Sec/Twnshp/Rge: 31-9S-22W
1980 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SUTOR E Well Number: 3
County: GRAHAM Total Vertical Depth: 4150 feet

Operator License No.: 31274
Op Name: HRBEK, R.L.
Address: RR 1, BOX 11
MERINO, CO 80741

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 250
Production: Size 4.5 feet: 3980
Liner: Size feet:

8134.88

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 3:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 04/17/2001 4:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 250' cwc. 4 1/2" set at 3980'.
Prod. Perf 3807' - 3824'.
Cement in braden head - could not pull pipe - squeezes N/A.
Fluid Level near 3000'.
Loaded 4 1/2" casing with 8 yards Redi-Mix - 10 yards by yield.
Plug complete.

INVOICED
DATE 5-04-01
INV. NO. 2001061742

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 1 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS VESPER UNIT #6-3.

Plugged through: CSG

District: 04

Signed *Carl Goodrow*

(TECHNICIAN)

PETROLEUM, INC

#3

SUTOR 'E'

31-9-22W

W2 NE SW

Contr. GARVEY DRILLING

GRAHAM

County

E 2386RB Comm.

Comp. 1-17-58

IP 58 BOPD/LANS

PERM PMP

Tops	Depth	Datum
ANH	1940	1416
TOP	3391	-1005
HEEB	3616	-1230
TOR	3641	-1255
LANS	3654	-1268
B/KC	3878	-1492
MARM	3972	-1586
CONG	4040	-1654
TD	4450	-1764

Casing

8" 250

4" 3980

DST 3655-3750, 510' SL GCM, BHP 1075#

DST 3750-98/1 HR, 35' MUD, BHP 575#


DST 3797-3818/1 HR, G/15", 2220' GSY OIL
BHP 1125#

DST 3824-38/1 HR, G/12", 3660' GSY OIL
BHP 1050#

DST 3838-3900/1 HR, 40' SL O & GCM, BHP
400#

VESPER POOL

CO 3918; 20/3819-24; FU
60 BOPH; 12/3807-10; ACID
5000; SWB 20 BOPH, NW



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS