

4-041401

9-3

15-065-03013-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 11-6-1957

N2 SW SW /4 SEC. 31, 09 S, 22 W
990 feet from S section line
4620 feet from E section line

Operator license# 9856

Lease Vesper WF (Sutor) well # 6-5

Operator: D.R. Well Operation, Inc.

County Graham

Address: 7585 W. Arkansas
Lakewood, Colorado 82032

Well total depth 4115 feet ^{133.73}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 251 feet
w/225 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 3 Month: September Year: 92

Plugging proposal received from: Herman Fellhaelter

Company: H. & C. Operation, Inc. Phone: 913-434-4501

Were: 4 1/2" casing set @ 3990' w/200 sx. cement. Perf. @ 3802' - 3863'. D.V. 1976' w/900 sx.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 3, Month: September, Year: 92

Actual plugging report: R.I.H. with tubing to 3815'. Spot 55 sx. cement w/100# hulls. Pull tubing to 2800'. Spot 55 sx. cement w/100# hulls. Pull tubing 1800'. Spot 60 sx. cement w/150# hulls to circulate cement to surface. P.O.O.H. with tubing. Hook-up to 4 1/2" casing, squeeze 80 sx. cement. Max. 500#. Shut in 250#. Hooked-up to 8 5/8" surface pipe. Pressured up 500#.

RECEIVED
STATE CORPORATION COMMISSION
9/28/92
SEP 28 1992

Remarks: Condition of casing(in hole):GOOD BAD X Any plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING X, CASING . Elevation: GL

I did [] did not [] observe the plugging.

Dennis L. Hamel

DATE 10-12-92
INV. NO. 36404

HO.

(agent)
Form CP-2/3