

9-3

4-041402

15-065-03014-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1-1-1957

1650 ~~1660~~ 2970 SE NE SW /4 SEC. 31, 09 S, 22 W
feet from S section line
feet from E section line

Operator license# 9856 Lease Vesper Unit (Sutor E-6) well # 6-6

Operator: D.R. Well Operation, Inc. County Graham

Address: 7585 W. Arkansas Well total depth 4071 feet ^{132.30}
Lakewood, Colorado 82032 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet
w/225 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 3 Month: September Year: 92

Plugging proposal received from: Herman Fellhaelter

Company: H. & C. Operation, Inc. Phone: 913-434-4501

Were: 4 1/2" casing set @ 3990' w/200 sx. cement. Perf. @ 3800' - 3850'. D.V. 1945' w/900 sx.
Order 275 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:45P.M., Day: 3, Month: September, Year: 92

Actual plugging report: R.I.H. with tubing to 3850'. Spot 55 sx. cement with 100# hulls. Pull tubing to 2850'. Spot 55 sx. cement with 100# hulls. Pulled tubing to 1850'. Spot 30 sx. cement with 100# hulls. to circulate cement to surface. P.O.O.H. with tubing. Hook-up to casing. Squeeze 20 sx. cement. Max. 1000#. Shut in 600#. Hooked-up to 8 5/8" surface pipe. Squeezed in 60 sx. cement w/100# hulls. Max. 300#. Shut in 200#.

RECEIVED
STATE CORPORATION COMMISSION

9/28/92
SEP 28 1992

Remarks: Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Dennis L Hamel

DATE 10-12-92
INV. NO. 36405

H/O (agent)