

15-065-03008-00-00

9-11

6 041229

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 12-28-57

SE SE NW, SEC. 31, T 9 S, R 22 W/E

2970 feet from S section line

3045 ^{KCC ZAP} 2970 feet from E section line

Lease Name Vesper ^{KCC ZAP} Well # 3-4

County Graham 124.80

Well Total Depth 3840 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264 w/170 sks

TECHNICIAN'S PLUGGING REPORT

Operator License # 9856

Operator: DR Well Oper Inc.

Name & Address 7585 W. Arkansas

Lakewood, Colo. 80226

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Ks.

Company to plug at: Hour: 8:00AM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Herman Fellhoelter

(company name) H and C Operating (phone) _____

were: 4 1/2 casing set at 384 w/100 sks cement: perfs at 3767.

Perf anhy at 1900; perf base dakota at 1075. Bad casing 1800 - 3500.

Perf base s.p. 250. Ordered 350 sks 65/35 poz 10% gel w/1/4 lb f.c.
plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 AM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 4 1/2 casing w/25 sks cement w/1/4 lb f.c.

plus pumped in add 225 sks cement w/1/4 lb f.c. and 5 sks hulls mixed in cement. Max 450 lb.

S.I. 300 lbs. Pumped in 8 5/8 casing w/60 sks cement w/1/4 lb f.c. and 0 sks hulls

mixed in cement. Max 450 lb. S.I. 300 lb.

RECEIVED
OCT 8 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did ~~not~~) observe this plugging.

DATE 10-10-90

INV. NO. 29611

9-11

Jub S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel