

To: 6 061935
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-11
API NUMBER 15-163, 21, 954-00-00 280 R
NW NW SE, SEC. 33, T 8 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914
Operator: H and C Oil Operating Inc.
Name & Address: Box 86
Plainville, Ks. 67663

2310 feet from S section line
2310 feet from E section line
Lease Name McMullin Well # 1
County Rooks 113.75
Well Total Depth 3500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number _____
Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: 8:30AM Day: 11 Month: August Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45AM Day: 11 Month: August Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 285' w/130 sks. 5 1/2" set at 3499' w/175 sks.

Top perf at 3249'. Plugged bottom w/sand and 5 sks cement to 3200'. Shot pipe two times and recovered 1120'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/400 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 6 1989 9/6/89

Remarks: By Allied Ran line to 1200'
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KANSAS

Signed Gilbert G. Scheck (TECHNICIAN)

INVOICED

DATE 9-11-89

INV. NO. 25866