

6030492

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22,706-00-00  
SCHNEIDER SECS. 35, T. 8 S, R. 17 (W)

2350 feet from S section line  
1040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Habe Well # 1

Operator: Oil Producers Inc. of Kansas  
Name & Address P.O. Box 8647  
Wichita, Kansas  
67208

County Rock 109.53

Well Total Depth 3370 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 213'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman & Jannitti Dily License Number 5122

Address Wichita, Kansas

Company to plug at: Hour: PM Day: 26 Month: 6 Year: 19 85

Plugging proposal received from Vernon Dunlap

(company name) Woodman & Jannitti (phone) \_\_\_\_\_

were: 8 5/8 act @ 213' w/ 140 sp. Spot cement plugs with Drill pipe with hole full of no less than 36 vis mud and no loss or gain of fluid. Order 190 of 50/50 per 60 gal 3 bcc 8 5/8 w.p. 1/2 Cell Flake allied Cmt. Co.

STATE CORPORATION COMMISSION

JUL 11 1985  
7/11/85  
Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:30 PM Day: 26 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Spot D.P. @ 1260' displace 25 cf. Cmt mix. laydown D.P. to 750' displace 100 cf. Cmt mix. + 1/2 Cell Flake laydown D.P. to 225' displace 40 cf. Cmt mix. laydown D.P. Push W.P. to Kelly depth. load hole to base of collar with 10 cf Cmt mix. Displace 15 cf Cmt mix. in Rathole with a joint of pipe. Plug complete

Remarks: Elev. 1920 KB Only 1257-92 no loss no loss of fluid with Cmt.  
(if additional description is necessary, use BACK of this form.)

INVOICED (did/did not) observe this plugging.

DATE 7-16-85

Signed Carl Goodnow 15  
(TECHNICIAN) 7-10-85

NO. 8964 JUL 31 1985 SEP 11 1985