

15-163-00714-00-00

4-032079

7-31-95

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1954

NW NE SE /4 SEC. 25, 08S, 18 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 5363 Lease: Vallette Well # 2  
Operator: Berexco, Inc. County: Rooks 111.28  
Address: P.O. Box 723 Well total depth 3424 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 104 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 31 Month: July Year: 1995

Plugging proposal received from: Curtis Gabel

Company: Berexco, Inc. Phone: \_\_\_\_\_

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Work string of tubing.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 01 1995  
SEP 01 1995

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 7:30 P.M., Day: 31, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 104' cwc with 100 sxs. 5 1/2" set at 3421' with 150 sxs. Squeezed from 2899' to surface with 1005 sxs cement blend. Test 8 5/8" to 500#. Ran tubing to 3420'. Displaced 115 sxs cement blend with 250# hulls mixed in, pulled tubing to 1700'. Displaced 140 sxs cement blend with 200# hulls mixed in, to circulate. Pulled tubing, tied onto 5 1/2". Squeezed with total of 280 sxs cement blend with 450# hulls mixed in to Max. P.S.I. 600#. Close in P.S.I. 200#. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ GL

**INVOICED**  
I did X / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

DATE 9-6-95  
INV. NO. 43406