

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03169-00-00
Spot: CSWSESE Sec/Twnshp/Rge: 25-8S-18W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: VALLETTE Well Number: 1
County: ROOKS Total Vertical Depth: 3418 feet

Operator License No.: 5363

Production Casing Size: 5.5 feet: 3408 w/150 sxs cmt

Op Name: BEREXCO, INC.

Surface Casing Size: 8.625 feet: 185 w/130 sxs cmt

Address: PO BOX 20380
WICHITA, KS 67208

\$111.09

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/05/2003 1:00 PM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO, INC.

Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 285 sxs 60/40 pozmix - 10% gel - 800# hulls.
Well squeezed at 2450'.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/05/2003 4:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 235' - 850' - 1400' - 1845'.
TIH with tubing to 3100' - mixed and pumped 100 sxs cement with 300# hulls.
Pulled up to 1600' - spotted 70 sxs cement with 300# hulls.
Pulled up to 600' and circulated cement up 5 1/2" with 50 sxs cement and 200# hulls.
Shut in 5 1/2" and continued with 60 sxs cement circulated up 8 5/8".
POOH. Topped off well with 5 sxs cement.


RECEIVED
MAY 09 2003
MAY 09 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-12-03

NO. 2003061509

MAY 06 2003

HARRY GORE

#1

VALLETTE

25-8-18W
SW SE SE

Contr. B & R DRILLING CO.

ROOKS

County

E. 1993 Comm.

Comp. 8-5-49 IP

200 BOPD

Tops	Depth	Datum
HEEB	3119	-1126
LANS	3154	-1161
ARB	3407	-1414
T.D.	3416	-1423

Casing

8" 185 1500' 01H/16 HRS.
 5" 3408 ACID 1000
 PMP 8 BOPH/15 HRS.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS