

10-12 15-163-03413-00-00

4-031869

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1955

SW SE NE /4 SEC. 25, 08 S, 18 W
2970 feet from S section line
990 feet from E section line

Operator license# 5285

Lease McMillen well # 1

Operator: Dane G. Hansen Trust

County Rooks

Address: P.O. Box 187
Logan, Kansas 67646

Well total depth 3432 feet ^{111.54}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 165 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 12 Month: October Year: 93

Plugging proposal received from: Rich Wallgren

Company: Dane G. Hansen Trust Phone:

Were: Order 300 sxs. 65/35 pozmix - 10% gel and 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 12, Month: October, Year: 93

Actual plugging report: 8 5/8" set @ 165' w/150 sxs. cwc. 5 1/2" set @ 3411' w/175 sxs. Circulate from 1029' to surface w/791 sxs. Perf's at 3154' - 3329'. Ran tubing to 2200' staged cement slurry to surface with total 300 sxs. cement blend with 500# hulls mixed in cement in cellar. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

NOV 05 1993
NOV 05 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: GL

I did observe the plugging. Carl Goodrow

INVOICED
DATE 11-8-93
INV. NO. 39165

(agent)
Form CP-2/3