

9-14 15-163-03414-00-00

4-071060

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 8-11-55

NE SE NE /4 SEC. 25, 08 S, 18 W
3630 feet from S section line
330 feet from E section line

Operator license# 5285

Lease McMillen well # 2

Operator: Dane G. Hansen Trust

County Rooks

Address: P.O. Box 187
Hays, Kansas 67601
Richard Wallgreen Sr.

Well total depth 3394 feet ^{110.30}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 14 Month: September Year: 93

Plugging proposal received from: Richard Wallgreen Sr.

Company: Dane G. Hansen Trust Phone: 913-689-4816

Were: 8 5/8" - 160' S.P. cwc. w/150 sxs. cement. 5 1/2" casing set @
3390' w/175 sxs. cement. Top stage cemented with 430 sxs. cement.
5 1/2" squeeze at 2522' w/50 sxs. 736' w/200 sxs. 2283' w/250 sxs.
2430' w/50 sxs. 740' w/300 sxs. 2130' w/300 sxs. 4 1/2" liner set @
2993' w/175 sxs. cement and 150 sxs. Casing good. Perf. 3299' - 2981'.
Proposal 225 sxs. 60/40 pozmix - 8% gel. - 5 sxs. hulls. Pump in with
pump truck. Pump in 4 1/2" casing w/15 sxs. cement followed with an
additional 185 sxs. cement w/hulls. Squeeze 5 1/2" x 8 5/8" annulus in
in cement. 4 1/2" x 5 1/2" annulus full of cement.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 14, Month: September, Year: 93

Actual plugging report: Hansen ordered 225 sxs. 60/40 pozmix - 8% gel. -
5 sxs. hulls. Pumped cement in casing with pump truck.

- 1) Pumped in 4 1/2" casing with 15 sxs. cement followed w/200 sxs. cement
w/5 sxs. hulls added.
- 2) 4 1/2" x 5 1/2" annulus full of cement.
- 3) Squeezed 5 1/2" x 8 5/8" annulus with no cement. Max. pressure 500
P.S.I. Shut in @ 500 P.S.I.

Remarks: Cemented by Allied Cement.

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did and not observe the plugging.

INVOICED
DATE 9-23-93
INV. NO. 38790

Marion J. Schmidt
(agent)

RECEIVED
STATE CORPORATION COM
SEP 22 1993
Sep 22, 1993
CONSERVATION DIVIS
Wichita, Kansas