

9-28

6 070864

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-01,027-00-01  
NW NW SE SEC. 26, T 8 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5635

Operator: The Gene Brown Company  
Name & Address: Drawer 220  
Plainville, Ks. 67663  
Thomas mM Brown

2310 feet from S section line

2310 feet from E section line

Lease Name Peter Dechant Well # 2 OWWO

County Rooks 35.00

Well Total Depth 1025 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated Went out of hole at 1025 ft. Decided to plug.  
Service

Plugging Contractor Halliburton Cement & Bills Well license Number

Address Hays, Ks. Codell, Ks.

Company to plug at: Hour: Am Day: 28 Month: Sept Year: 19 90

Plugging proposal received from Tom Brown

(company name) The Gene Brown Company (phone)

were: 8 5/8 s.p. set at 230 ft w//N.A. Well was drilled. Re-entered OWWO and drilled out of hole at 1025 and decided to plug. Proposal 200 sks 60/40 poz 6% gel 3% ca cl and 8 5/8 plug. Spot with drill stem. Circulate heavy mud between all plugs. 50 sks at 1020. 100 sks at 770 w/f.c. 40 sks at 270. 10 sks at 40. No rathole.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 9:40AM Day: 28 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Brown Company ordered 200 sks 60/40 poz 6% gel 3% ca cl and 8 5/8 plug. Spotted cement with drill stem, circulated heavy mud between all plugs.

1st plug 50 sks at 1020. 2nd plug 100 sks w/1 sk. F.C. at 770.

3rd plug 40 sks at 270 4th plug 10 sks at 40. No rathole

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: By Halliburton Cement.

(If additional description is necessary, use BACK of this form.)

INVOICED

XXXXXX (do not) observe this plugging. CONSERVATION DIVISION  
Wichita, Kansas

DATE 10-18-90

INV. NO. 29636

Signed

Marion J. Schmidt  
(TECHNICIAN)