

6 020544

Code  
Payee

80-7033

B842638

7-17

API NUMBER 15-

NA

15-163-01414-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW SW SE, SEC. 33, T 8 S, R 19 WAE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Operator: Phillips Pet Co.

Name & Address: Route #3 Box 20A

Great Bend, Ks. 67530

Lease Name Fidelis Well # 1

County Rooks 111.67

Well Total Depth 3436 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1463 w/800 sks

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Allied Russell, Ks. License Number

Address

Company to plug at: Hour: 8:00AM Day: 17 Month: July Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 5 1/2 casing set at 3443 w/200 sks cement.

Perf at 3328 - 3443. Shot casing and recovered 2615 of 5 1/2 casing.

Ordered 300 sks 65/35 poz 10% gel w/1/4 lbs. f.c. plus 5 sks hulls.

Plugging Proposal Received by

(TECHNICIAN) Gilbert Baltazor Dennis Hamel

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30PM Day: 17 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Hooked up to 8 5/8 surf casing: pumped in 300 sks

of 65/35 popz 10% gel w/1/4 lb. of f.c. plus 500 lbs. of hulls mixed in

first 50 bbl of cement slurry. Max psi 700 lbs. S.I. psi 400 lbs.

STATE CORPORATION COMMISSION

JUL 25 1990

6/25/90

CONSERVATION DIVISION

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging.

DATE: 7-30-90

INV. NO. 28822

Signed Dennis L. Hamel

(TECHNICIAN) Dennis Hamel