

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21323-00-00  
Spot: NENENE Sec/Twnshp/Rge: 30-7S-17W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: GRIFFITH Well #: 4  
County: ROOKS Total Vertical Depth: 3315 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3261	0	150 SX CMT
SURF	8.625	1220	0	450 SX CMT

*\$ 107.74*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2007 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 415 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Operator elected to use all cement.  
Squeeze job: Bond Log TOC 8 5/8" - 5 1/2" 500'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/26/2007 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

LK Wireline perforated two holes at 425'.  
Allied pumped 50 sxs 60/40 pozmix down 5 1/2" casing, followed with 350 sxs 60/40 pozmix - 4% gel and 600# hulls.  
Cement circulated out 8 5/8" - shut pressured casing to Max. P.S.I. 1000#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3261	3307	OH	

**INVOICED**  
DATE 10/3/07  
INV. NO. 2008060537

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Richard Williams*

(TECHNICIAN)

OCT 01 2007

STATE CORPORATION COMMISSION  
Form CP-2/3

OCT 03 2007

CONSERVATION DIVISION  
WICHITA, KS

RIM OIL CO.  
512 S. WYOMING  
PLAINVILLE, KS. 67663

REPLACEMENT CARD:  
#4 GRIFFITH

30-7-17W  
NE NE NE

CONTR RANGER DRILLING CO. INC. CTY ROOKS

GEOL KENNETH VEHIGE FIELD RIFFE

E 1785 KB E 9/20/81 CARD  
T780 GL CM ISSUED 1/21/82 IP P 45 BOPD & WTR  
ARB OH 3261-3315

+	+	+	
+	+	+	
+	+	+	

API 15-163-21,323

LOG	TOPS	DEPTH	DATUM
TOP		2704	- 919
KH		2799	-1014
QH		2854	-1069
HEEB		2914	-1129
TOR		2937	-1152
LKC		2958	-1173
B KC		3184	-1399
MARM		3200	-1415
REW ARB		3253	-1468
ARB		3260	-1475
RTD		3307	-1522
LTD		3315	-1530

8-5/8" 1220, 5 1/2" 3261  
NO DST'S  
MICT - CO, (ARB OH), SWB DWN W/GSO, NAT  
POP, P 45 BOPD & WTR

CORRECTION: 3/4/82 - WAS NE NW NE.

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS