

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22017-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 18-7S-17W
1730 feet from S Section Line, 3570 feet from E Section Line
Lease Name: MILLER Well #: 2
County: ROOKS Total Vertical Depth: 3334 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3332	0	130 SX
SURF	8.625	1264	0	475 SX

\$ 108.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2007 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 390 sxs 60/40 pozmix - 4% gel - 600# hulls.
Operator elected to use all cement.
Squeeze job: 2377' to 2699' w/200 sxs cwc.
8 5/8" - 5 1/2" cemented to surface.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2007 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 335 sxs 60/40 pozmix - 4% gel with 600# hulls.
Max. P.S.I. 1000#. S.I.P. 200#. Released pressure.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3332	3336		

INVOICED
DATE 10-3-07
INV. NO. 2008060537

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

OCT 01 2007

Form CP-2/3
OCT 03 2007
CONSERVATION DIVISION
WICHITA, KS

AMERICAN LARIAT, INC.

P.O. BOX 936

#2 MILLER

18-7-17W

HAYS, KS 67601

3550' FNL &

CONTR PIONEER DRILLING COMPANY

CTY


ROOKS

1710' FWL, SEC

GEOLOGICAL

FIELD

RIFFE



ELV 1832 KB SPD 8/22/83 CARD ISSUED 11/17/83 IP P 50 BOPD, NW

ARB OH 3332-3336

API 15-163-22,017

LOG	Tops	Depth/Datum
SC	1259 + 573
TOP	2764- 932
HEEB	2973-1141
LANS	3017-1185
BKC	3244-1412
ARB	3330-1498
RTD	3334-1502
DDTD	3336-1504

8 5/8 " 1264/475SX; 5 1/2 " 3332/130SX

NO DST'S

MICT - CO, (ARB OH), DD 3336 TD, SWB DWN, GSO, NAT, POP,
P 50 BOPD, NW, 9/14/83

NOTE: CORRECTION 4/28/83 - ORIGINALLY FIRST REPORTED IN
SW NE SW

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS