

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-151-22226-00-00
 Spot: NWNW Sec/Twnshp/Rge: 32-29S-12W
 660 feet from N Section Line, 660 feet from W Section Line
 Lease Name: PERRY Well #: 1-32
 County: PRATT Total Vertical Depth: 4650 feet

Operator License No.: 5047
 Op Name: RUPE OIL COMPANY, INC.
 Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2750		WITH 2 SX CMT
CIBP		2898		
PROD	4.5	3851	2400	WITH 100 SX CMT
SURF	8.625	285		WITH 250 SX CMT

\$151.13

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/20/2007 2:40 PM
 Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
 Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 2750' WITH 2 SX CMT. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
 Date/Time Plugging Completed: 09/20/2007 3:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 2750' WITH 2 SX CMT. 1ST PLUG AT 760' WITH 10 SX GEL & 50 SX CMT.
 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3776	3788		
2809			
2802	2806		INDIAN CAVE

INVOICED
 DATE 10/3/07
 INV. NO. 2008060539

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Eric MacLaren
 (TECHNICIAN)

KANSAS CORPORATION COMMISSION
 Form CP-2

OCT 03 2007

CONTO...
 67207

PT