

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-111-20411-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 12-18S-11E  
1620 feet from N Section Line, 920 feet from W Section Line  
Lease Name: KARR Well #: 5-12-18-11  
County: LYON Total Vertical Depth: 2167 feet

Operator License No.: 33166  
Op Name: CALPINE NATURAL GAS LP  
Address: 1200 17TH STREET, #770  
DENVER, CO 80202

| String | Size  | Depth (ft) | Pulled (ft) | Comment    |
|--------|-------|------------|-------------|------------|
| PROD   | 5.5   | 2155       |             | 387        |
| SURF   | 9.625 | 40         |             | 40 SXS CMT |
| T1     | 2.875 | 2100       |             |            |

\$ 70.43

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/15/2007 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: STEVEN R. HASH, P.E. Company: \_\_\_\_\_ Phone: (918) 599-9400

Proposed Plugging Method: PUMP VIA TBG 50FT CMT PLUG #1 2040-1990, PULL TBG TO 1330, PUMP VIA TBG 100 FT. CMT PLUG 1330-1230, PULL TBG PUMP 100 TO SURFACE, CUT OFF CSG & WELD ON PLATE WITH NAME & DATE, MUD BEWTEEN PLUGS.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/21/2007 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2035' pumped 15 sxs cement, pulled tubing to 1332', pumped 15 sxs cement, pulled tubing to 150', pumped 25 sxs cement to surface, gel spacers between cement plugs.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2067 | 2069 |      |          |
| 2046 | 2048 |      |          |
| 2041 | 2043 |      |          |
| 2039 | 2040 |      |          |
| 2033 | 2034 |      |          |
| 2021 | 2025 |      |          |

RECEIVED  
KCC DISTRICT #3  
SEP 04 2007 MH  
CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 10 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED  
DATE 10/12/07  
INV. NO. 2008060558

District: 03

Signed Mike Heffern  
(TECHNICIAN)

*PH*