

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-01001-00-01
Spot: N2NENE Sec/Twnshp/Rge: 29-33S-2E
5043 feet from S Section Line, 707 feet from E Section Line
Lease Name: MAY SHEPHERD Well #: 1
County: SUMNER Total Vertical Depth: 3575 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3380		
CIBP		3404		
PROD	5.5	3575	1521	100 SX CMT
SURF	8.625	212		175 SX CMT

\$ 116.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2007 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING AND SALVAGE Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3250' AND 5 SKS CMT, REC PIPE, CIRC CMT FROM 300-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/25/2007 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3250' AND CAPPED WITH 5 SKS OF CMT. THE PIPE WAS RECOVERED FROM 1431 AND PULLED FROM THE WELL BORE. TUBING WAS RUN TO 307' WHERE CMT WAS CIRCD TO SURFACE - 97.22374,37.15814.

Perfs:

Top	Bot	Thru	Comments
3569	3570		
3546	3550		
3342	3346		
3328	3332		
3318	3320		

INVOICED
DATE 10/15/07
INV. NO. 2008060564

Remarks: COPELAND ACID 110 SKS 60/40 4% GEL TICKET #32420

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2007
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3