

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21805-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 28-33S-2E
5000 feet from S Section Line, 5183 feet from E Section Line
Lease Name: SWANSON Well #: 1
County: SUMNER Total Vertical Depth: 3465 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3050		
PROD	4.5	3465		
SURF	8.625	250		

\$ 112.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2537

Proposed Plugging Method: PERFS 2364'-73. CIBP @ 3050', 3324'-34' AND 3336'-76'. SAND BACK TO 2300' AND 4 SKS, REC PIPE, CIRC CMT 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/25/2007 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 2300', AND CAPPED WITH 4 SKS OF CMT. THE PIPE WAS RECOVERED FROM 1321', AND PULLED FROM THE WELL BORE. TUBING WAS RUN TO 307', WHERE CMT WAS CIRCD TO SURFACE. - 97.22028,37.15799.

Perfs:

Top	Bot	Thru	Comments
3336	3376		
3324	3334		
2364	2373		

INVOICED
DATE 10/15/07
INV. NO. 2008060564

Remarks: COPELAND ACID 32421 100 SKS 60/40 4% GEL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 09 2007

CONSERVATION DIVISION
WICHITA, KS