

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23105-00-00  
Spot: W2NENW Sec/Twnshp/Rge: 16-27S-22E  
350 feet from N Section Line, 1950 feet from W Section Line  
Lease Name: KELLER Well #: 16-21  
County: BOURBON Total Vertical Depth: 775 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	771		
SURF	8.625	20		
T1	2.375	706		

\$ 35.00

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2007 11:15 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 771' THAT HAD BEEN CMEENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/01/2007 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI. APPROXIMATELY 75 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
682	685		
632	633		
625	627		
549	551		
533	535		
510			
496	498		
446	449		
301	312		
298	301		

RECEIVED  
KCC DISTRICT #3

OCT 3 2007

CHANUTE, KS

CPT

INVOICED  
DATE 10/15/07  
INV. NO. 2008060572

Remarks: GPS LOCATION OF WELL 095.00870 W & 37.70279 N.

Plugged through: CSG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)