

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23110-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 4-27S-22E
1500 feet from S Section Line, 330 feet from W Section Line
Lease Name: KELLER Well #: 4-13
County: BOURBON Total Vertical Depth: 887 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	881		
SURF	8.625	21		
TI	2.375	842		

\$ 35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/01/2007 10:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 881' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2007 10:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800 PSI. 84 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3
OCT 3 2007 CPT
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
801	804		
764	766		
750	752		
743	745		
590			
559	561		
422	425		
412	415		

INVOICED
DATE 10/15/07

Remarks: GPS WELL LOCATION 095.01452 W & 37.72207 N.

INV. NO. 2008060572

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
Form CP-2/3
KANSAS CORPORATION COMMISSION
OCT 09 2007
CONSERVATION DIVISION
WICHITA, KS