

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23130-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 9-27S-22E  
330 feet from S Section Line, 2000 feet from E Section Line  
Lease Name: KELLER Well #: 9-34  
County: BOURBON Total Vertical Depth: 777 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	774		
SURF	8.625	22		
T1	2.375	697		

\$ 35.00

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2007 2:30 PM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: \_\_\_\_\_ Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 774' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/01/2007 3:15 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI.

RECEIVED  
KCC DISTRICT #3  
  
OCT 3 2007 CPT  
  
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
662	664		
655	658		
618	620		
598	600		
430			
415	417		
280	283		
268	271		

INVOICED  
DATE 10/15/07

Remarks: THIS WELL GPS'D AT 37.70472 N & 095.00397 W.

INV. NO. 2008060572

Plugged through: CSG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CB-278  
OCT 09 2007  
CONSERVATION DIVISION  
WICHITA, KS