

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21197-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 21-24S-16W  
990 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: LUNZ B Well #: 1-21  
County: EDWARDS Total Vertical Depth: 4454 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4450	2050	WITH 225 SX CMT
SURF	8.625	265		WITH 210 SX CMT <b>\$144.76</b>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2007 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4240' & 4 SX CMT. PLUG AT 1110' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/25/2007 2:59 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 4240' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1110' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4291	4295		

**INVOICED**  
DATE 10/15/07  
INV. NO. 2008060573

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 09 2007

CONSERVATION DIVISION  
WICHITA, KS