

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20614-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 35-23S-17W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WHITE ELAINE Well #: 1-35  
County: PAWNEE Total Vertical Depth: 4361 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4356	2440	WITH 150 SX CMT
SURF	8.625	253		WITH 225 SX CMT

\$ 141.73

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2007 11:20 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT. PLUG AT 1150' WITH 15 SX GEL - 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2007 12:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:  
SANDED TO 4300' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1150' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4291	4296		
4286	4289		
4252	4256		

INVOICED  
DATE 10/15/07  
INV. NO. 2008060573

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01  
**RECEIVED**  
OCT - 2 2007  
KCC Dodge City

Signed \_\_\_\_\_  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3  
OCT 09 2007  
CONSERVATION DIVISION  
WICHITA, KS

*Handwritten initials/signature*