

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 055-21612 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 2/12/98

Well Operator: Lario Oil & Gas Co. KCC License #: 5214  
(Owner / Company Name) (Operator's)

Address: 301 S Market St. City: Wichita

State: Ks. Zip Code: 67202 Contact Phone: (316) 265 - 5611

Lease: Baker Well #: 15-8 Sec. 15 Twp. 23 S. R. 3334  East  West

E2 - SE - NW Spot Location / QQQQ County: Finney Co

90 1920 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

170 2200 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 1828' Cemented with: 700 (Circ'd) Sacks

Production Casing Size: 5 1/2" Set at: 4900' Cemented with: 665 (TOC- 2300') Sacks

List (ALL) Perforations and Bridgeplug Sets: 4654'- 56', 4730'- 36', 4808'- 14', 4816'- 18', 4844'- 48'

Elevation: 2938' ( G.L. /  K.B.) T.D.: 4900' PBTD: 4848' Anhydrite Depth: N.A.  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 30 sks cement mixed with 2 sks of hulls. 1st plug at 1860' 20 sks of gel and 50 sks of cmt. 2nd plug 1050' 40 sks of cmt. 3rd plug at 40' 20 sks of cmt.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

OK to pay

SEP 24 2007

G

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Larry Karlin

Phone: (785) 650 - 2029

Address: 1807 Pioneer Rd. Garden City, Ks. 67601 City / State: Ks

Plugging Contractor: Allied Cementing Co. KCC License #: 99996  
(Company Name) (Contractor's)

Address: Oakley Ks Phone: (785) 672 - 3452

Proposed Date and Hour of Plugging (if known?): A.S.A.P. 10-9-07 8:00AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/21/07 Authorized Operator / Agent: Larry Karlin  
(Signature)

We'll already plugged - KCC-Dlg Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 16 2007  
CONSERVATION DIVISION  
WICHITA, KS