

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 181-20379-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Rosewood Resources, Inc. KCC License #: 33019
(Owner / Company Name) (Operator's)

Address: 2711 N. Haskell Ave., Suite 2800, LB #22 City: Dallas

State: Texas Zip Code: 75201 Contact Phone: (970) 324 - 1686

Lease: Bradshaw Well #: 1-15 Sec. 15 Twp. 10 S. R. 39 East West

SE - NW - NW - NW Spot Location / QQQQ County: Sherman

400 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

400 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 5 1/2" Set at: 232' Cemented with: 40 Sacks

Production Casing Size: 2 7/8" Set at: 948' Cemented with: 45 Sacks

List (ALL) Perforations and Bridgeplug Sets: 774' to 800'

Elevation: 3603' (G.L. / K.B.) T.D.: 980' P.B.T.D.: 960' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump 17 sacks with 10% gel and 50lbs cotton seed hulls down 5.5" surface casing. Pump 21 sacks with 10% gel 100lbs of cotton seed hulls in lead cement down 2 7/8" casing. Cut off casing 5' below ground level.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Tom Roelfs

Phone: (970) 324 - 1686

Address: PO Box 926 City / State: St. Francis, KS 67756

Plugging Contractor: Lonhorm Cementing Co. Advanced Drilling KCC License #: 33532
(Company Name) (Contractor's)

Address: 44963 County Road K, Yuma, Colorado, 80759 Phone: (970) 848 - 0799

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/10/2007 Authorized Operator / Agent: Tom W. Roelfs
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 11 2007
CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ROSEWOOD RESOURCES, INC.
2711 N HASKELL STE 2800 LB # 22
DALLAS, TX 75204

October 17, 2007

Re: BRADSHAW #1-15
API 15-181-20379-00-00
15-10S-39W, 400 FNL 400 FWL
SHERMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 14, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond

Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550