

To: 6 041319  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-28 224 R  
API NUMBER 15- 163-23,153-00-00  
NW NE SE, SEC. 25, T 10 S, R 18  W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4868

2310 feet from S section line

990 feet from E section line

Operator: Asher Asso. Inc.

Lease Name Schmidt Well # 1

Name & Address 7340 E. Caley Ave. #310

County Rooks 119.60

Englewood, Colorado 80121

Well Total Depth 3680 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 271' w/160 sx.

Abandoned Oil Well Gas Well Input Well SWD Well D&A  X

Other well as hereinafter indicated

Plugging Contractor Vonfeldt Drilling Company License Number 9431

Address

Company to plug at: Hour: 1:15P.M. Day: 28 Month: 3 Year: 19 91

Plugging proposal received from Darrell Krier

(company name) Vonfeldt Drilling Company (phone)

were: Order 225 sx. cement 60/40 pozmix - 6% gel. w/1/4# F.C. Heavy mud between all plugs. Pump cement down drill pipe.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None  X

Operations Completed: Hour: 1:15P.M. Day: 28 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 25 sx. @ 3624'

25 sx. @ 1375'

100 sx. @ 800'

40 sx. @ 300'

10 sx. @ 40'

15 sx. in Rathole. 10 sx. Mousehole.

RECEIVED  
STATE CORPORATION COMMISSION

08-23-1991  
AUG 23 1991

Wichita Kansas

Remarks: Cementing Co: Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have supervised this plugging.

DATE 9-5-91

INV. NO. 32923

Signed Dennis L. Hamel (TECHNICIAN)