

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21, 81600-00

SW-SE-NE, Sec. 33, T 10 S, R 18 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

Lease Name WARREN VINE Well # 1-33

Operator: DON E PRATT

County ROCKS

Name & Address BOX 370

Well Total Depth 3642 feet

HAYS, KANSAS  
67601

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MURFIN DRILLING License Number 608

Address 617 UNION CRT. BLDG. WICHITA, KANSAS 67202

Company to plug at: Hour: 8:30 PM Day: 18<sup>th</sup> Month: OCT Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO BERNIE MEYERS

(company name) 617 UNION CRT. BLDG. WICHITA, MO. (phone) 913-743-2850

were: 8 5/8" - 209 FT SP. CUC w/ 165<sup>ST</sup> COMMON QUICK SET (BY ALLIED)

ORDER 180<sup>ST</sup> 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 1380 FT w/ 20<sup>ST</sup> CNT. -> 2<sup>ND</sup> PLUG @ 810 FT w/ 100<sup>ST</sup> CNT.

3<sup>RD</sup> PLUG @ 240 FT w/ 40<sup>ST</sup> CNT. -> 4<sup>TH</sup> PLUG <sup>SOLID BRIDGE</sup> HULLS-PLUG @ 40 FT w/ 10<sup>ST</sup> CNT.

10<sup>ST</sup> IN RAT HOLE (CIRCUMFERE)

Signed M. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:59 PM Day: 18<sup>th</sup> Month: OCT. Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 209 FT SP. CUC w/ 165<sup>ST</sup> (BY ALLIED)

ORDERED 180<sup>ST</sup> 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1<sup>ST</sup> PLUG @ 1380 FT w/ 20<sup>ST</sup> CNT. -> 2<sup>ND</sup> PLUG @ 810 FT w/ 100<sup>ST</sup> CNT.

3<sup>RD</sup> PLUG @ 240 FT w/ 40<sup>ST</sup> CNT. 4<sup>TH</sup> PLUG - <sup>SOLID BRIDGE</sup> HULLS-PLUG @ 40 FT w/ 10<sup>ST</sup> CNT.

10<sup>ST</sup> IN RAT HOLE (CIRCUMFERE)

Remarks: MR. MEYERS SAID THEY COULDN'T FIND ARDUCKIE  
SO THEY PLUGGED WELL.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1982

10-26-1982  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as stated and that I (did  did not) observe this plugging.

INVOICED

Signed M. Schmidt  
(TECHNICIAN)

DATE 11-16-82

FORM CP-2/3  
Rev. 9-82

INV. NO. 1622-W