

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22461-00-00
Spot: NENWNW Sec/Twnshp/Rge: 34-14S-21W
4920 feet from S Section Line, 4150 feet from E Section Line
Lease Name: BEFORT TRUST Well #: 1-34
County: TREGO Total Vertical Depth: 3958 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3953	2830	150 SX
SURF	8.625	223	0	150 SX

\$128.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2007 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2007 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Cut casing 5 1/2" at 2830'.
Pulled casing to 1450' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled casing to 600' - pumped 40 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled casing to 150' - circulated cement 60/40 pozmix - 4% gel with 90 sxs.
Pulled all casing. Open hole - pumped 30 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3749	3764		

INVOICED
DATE 9/24/07
INV. NO. 2008060465

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Pat Bedore PIRT I

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

SEP 20 2007

CONSERVATION DIVISION
WICHITA, KS

SEP 18 2007