

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23334-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 18-10S-23W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: CRONN Well #: 18-2
County: GRAHAM Total Vertical Depth: 4145 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT STREET, SUITE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		

134.71

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/13/2007 3:15 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 09/13/2007 6:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2125' w/25 sxs.
2nd. Plug at 1225' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 9/24/07
INV. NO. 2008060464

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 20 2007

CONSERVATION DIVISION
WICHITA, KS

SEP 19 2007

PRG