

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-26993-00-00
Spot: SWNESW Sec/Twnshp/Rge: 31-23S-19E
1576 feet from S Section Line, 3793 feet from E Section Line
Lease Name: MCINTYRE Well #: 45
County: ALLEN Total Vertical Depth: 948 feet

Operator License No.: 33805
~~31708~~
Op Name: ENSMINGER-KIMZEY, A GENERAL PA
Address: PO BOX 267
COLONY, KS 66015

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	948	0	
STRL	7	20	0	

\$ 35.00

Well Type: OIL UIC Docket No: 33805 Date/Time to Plug: 08/27/2997 8:00 AM
Plug Co. License No.: 31708 Plug Co. Name: ENSMINGER-KIMZEY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DAVE KIMZEY Company: KIMZEY-ENSMINGER Phone: (620) 496-2535

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 948' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2007 9:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 925'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

AUG 29 2007 CPT

CHANUTE, KS

INVOICED
DATE 9/21/07
INV. NO. 2008060448

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA GPS.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

TBG