

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27214-00-00
Spot: NENWNE Sec/Twnshp/Rge: 30-25S-14E
5060 feet from S Section Line, 1540 feet from E Section Line
Lease Name: TOWN Well #: 3
County: WOODSON Total Vertical Depth: 1605 feet

Operator License No.: 33119
Op Name: HEAT CAN OIL, LLC
Address: 7430 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	40	0	

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/07/2007 11:00 AM
Plug Co. License No.: 33193 Plug Co. Name: SMITH, KRIS DBA J & K OIL
Proposal Rcvd. from: DICK CORNELL Company: HEAT CAN Phone: (620) 431-6027

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASED BORE TO 1605'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 800', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2007 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS WASHED INTO THE BORE TO 1500'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 1500'. THE 1" WAS PULLED TO 800' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 250' CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED
DATE 9/21/07
INV. NO. 2008060451

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN) RECEIVED

KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]