

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-28464-00-00
Spot: SENESW Sec/Twnshp/Rge: 36-24S-17E
2145 feet from S Section Line, 2705 feet from E Section Line
Lease Name: H STRANGHOLDER Well #: A-2
County: ALLEN Total Vertical Depth: 827 feet

Operator License No.: 5602
Op Name: N & B ENTERPRISES, INC.
Address: PO BOX 812
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	760	0	
SURF	7	20	0	

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2007 8:30 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: RICHARD BURRIS Company: N & B ENTERPRISES, INC Phone: (620) 431-6424

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 760' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2007 9:50 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUM0P TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI. 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007

CHANUTE, KS

CPT

INVOICED
DATE 9/21/07
INV. NO. 2008060452

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS

PRG