

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-28470-00-00
Spot: SENESW Sec/Twnshp/Rge: 36-24S-17E
1880 feet from S Section Line, 3180 feet from E Section Line
Lease Name: H STRANGHONER Well #: B-3
County: ALLEN Total Vertical Depth: 829 feet

Operator License No.: 5602
Op Name: N & B ENTERPRISES, INC.
Address: PO BOX 812
CHANUTE, KS 67220

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		20		

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2007 9:50 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: RICHARD BURRIS Company: N & B ENTERPRISES, INC. Phone: (620) 431-6424

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 760' THAT HAD BEEN CEMENTED IN FROM BPTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2007 10:40 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CAING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS SHUT IN AT 250 PSI. APPROXIMATELY 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED
DATE 9-21-07
INV. NO. 2008060452

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PRG