

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-01897-00-01

Spot: NWNWNW

Sec/Twnshp/Rge: 2-25S-17E

5059 feet from S Section Line, 4698 feet from E Section Line

Lease Name: PIQUA GAS STORAGE

Well #: 3

County: ALLEN

Total Vertical Depth: 911 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPEL

Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	875		189
SURF	8.25	9		

\$ 35.00

Well Type: GSO

UIC Docket No:

Date/Time to Plug: 08/16/2007 8:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: SOUTHERN STAR GAS PIPELINE, I Phone: (785) 448-4816

Proposed
Plugging
Method:

CLEAN OUT TO T.D. SET RETAINER. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW
SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/16/2005 10:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

A RETAINER WAS INSTALLED AT 850'. 10 SACKS OF CEMENT WERE SQUEEZED THROUGH THE RETAINER AT 1250 PSI. TUBING WAS RAN INTO THE WELL TO T.D.. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE CAING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE CASING WAS THEN SQUEEZED TO 500PSI AND THE WELL WAS SHUT IN.

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED

DATE 9-21-07

INV. NO. 2008060457

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS

pb