

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-28435-00-00
Spot: NENWNE Sec/Twnshp/Rge: 22-23S-18E
5110 feet from S Section Line, 930 feet from E Section Line
Lease Name: CHARLES BAKER Well #: 5
County: ALLEN Total Vertical Depth: 1362 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPEL
Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1358		
PROD	2.78	1362		145 SX
SURF	6.5	20		

\$ 44.27

Well Type: SWD UIC Docket No: D26576.0 Date/Time to Plug: 08/13/2007 8:30 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Revd. from: BERNIE ROCKERS Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 08/14/2007 11:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN TO 1300' INSIDE THE 2 7/8" CASING. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 1300'. THE CEMENT WAS ALLOWED TO SET UP FOR 24 HOURS. 1" PIPE WAS THEN RAN TO TAG THE SET CEMENT AT 1225'. CEMENT WAS THEN PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" WAS REMOVED AND DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS


INVOICED
DATE 9/21/07
INV. NO. 2008060457

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

SEP 19 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

TBG