

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19424-00-01

Spot: NWSE

Sec/Twnshp/Rge: 3-25S-17E

2478 feet from S Section Line,

2037 feet from E Section Line

Lease Name: PIQUA GAS STORAGE

Well #: 13

County: WOODSON

Total Vertical Depth: 906 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPEL

Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.63	887		278 SX
SURF	10	10		

\$35.00

Well Type: GSO

UIC Docket No:

Date/Time to Plug: 08/23/2007 7:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: SOUTHERN STAR

Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/23/2007 9:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

A RETAINER WAS INSTALLED AT 870' INSIDE THE CASING. 10 SACKS OF CEMENT WERE SQUEEZED THROUGH THE RETAINER AT 700 PSI. TUBING WAS RAN INTO THE WELL TO 870'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPALCEMENT WAS FILLED. THE WELL WAS SQUEEZED TO 300 PSI AND SHUT IN.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED

DATE 9/21/07

INV. NO. 2008060457

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS

PKT