

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19433-00-01
Spot: SENENE Sec/Twnshp/Rge: 3-25S-17E
4038 feet from S Section Line, 223 feet from E Section Line
Lease Name: PIQUA GAS STORAGE Well #: 19
County: WOODSON Total Vertical Depth: 933 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPEL
Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 7 | 906 | | 172 SX |
| SURF | 10 | 27 | | |

\$35.00

Well Type: GSO UIC Docket No: Date/Time to Plug: 08/21/2007 2:00 PM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: BERNIE ROCKERS Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 08/21/2007 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

A RETAINER WAS INSTALLED IN THE CASING AT 885'. 10 SACKS OF CEMENT WERE SQUEEZED THROUGH THE RETAINER AT 800 PSI. TUBING WAS RAN INTO THE WELL TO 885'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED. THE WELL WAS SQUEEZED TO 250 PSI AND SHUT IN. 157 SACKS OF CEMENT WERE PUNPED INTO THIS WELL

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED
DATE 9/21/07
INV. NO. 2008060457

Remarks: THIS WELL WAS ORIGINALLY NAMED PIQUA NO.1.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

SEP 19 2007

CONSERVATION DIVISION
WICHITA, KS