

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-19435-00-01

Spot: NESWNE

Sec/Twnshp/Rge: 3-25S-17E

3380 feet from S Section Line, 1544 feet from E Section Line

Lease Name: PIQUA GAS STORAGE

Well #: 20

County: WOODSON

Total Vertical Depth: 923 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPEL

Address: 4700 HIGHWAY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	905		182 SX
SURF	10	25		

\$ 35.00

Well Type: GSO

UIC Docket No:

Date/Time to Plug: 08/21/2007 8:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: SOUTHERN STAR

Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 08/21/2007 10:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

A RETAINER WAS INSTALLED IN THE 7" CASING AT 885'. 10 SACKS WERE SQUEEZED THROUGH THE RETAINER AT 750 PSI. TUBING WAS RAN TO 885'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE WELL WAS SQUEEZED TO 250 PSI AND SHUT IN. 158 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED  
KCC DISTRICT #3

SEP 12 2007 CPT

CHANUTE, KS

INVOICED  
DATE 9/21/07  
INV. NO. 2008060457

Remarks: THIS WELL WAS ORIGINALLY NAMED PIQUA NO.2.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

SEP 19 2007

CONSERVATION DIVISION  
WICHITA, KS