

To: 6 031199
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-30
API NUMBER 15-163-20792-00-00
N/2 NW NE, SEC. 2, T. 10 S, R. 19 W/E
4950 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Sutor Well # 1

Operator: Graves Drilling Co. Inc.
Name & Address: 151 N. Main Suite 850
Wichita, Ks. 67202

County Rooks 122.20
Well Total Depth 3760 feet

RECEIVED
STATE CORPORATION COMMISSION
01-18-1989
JAN 28 1989

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 30 Month: Nov Year: 19 88

Plugging proposal received from Duntz

(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 247' w/175 sks. 5 1/2" set at 3521' w/75 sks.

Perfs at 3425' - 29'. Order sand and common cement. Pull pipe. Order 200 sks
65/35 Poz 10% Gel 2% Dical 500# Hulls. Allied Cement Co. Denny's Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30PM Day: 30 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3370' w/5 sks Common Cement on sand w/bailer

Recovered pipe w/shots at 890', 1600', and 1800'. Squeezed 8 5/8" w/200 sks
Cement Blend w/500# Hulls mixed into max psi 900#. Close in psi 400#. Plug
complete. Wire ran to anhydrite.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(copy to contractor) observe this plugging.

DATE 1-19-89
INV. NO. 23663

Handwritten initials/signature

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow