

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 1 Twp. 10S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE

Lease Owner Davis Bros.

Lease Name Mayhew "B" Well No. 1

Office Address 510 McFarlin Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed July 6 1962

Application for plugging filed July 9 1962

Application for plugging approved July 9 1962

Plugging commenced July 9 1962

Plugging completed July 10 1962

Reason for abandonment of well or producing formation Dropped 4 1/2" casing in hole. Unable to recover

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	164'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 1980', set plug, cemented with 25 sacks

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks

Filled hole with heavy drilling mud to 180', set plug, cemented with 15 sacks

Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1962
08-06-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1962

My commission expires January 3, 1966 Notary Public.



15-163-19362-00-00

DRILLER'S WELL LOG

Davis Area.

Hayhoe #3 # 1 well located in
 G NW SW, Section 1-102-10W
 Rooks County, Kansas

Commenced: June 26, 1962
 Completed: July 6, 1962
 Elevation: 2187 D. F.

Casing: 8 5/8" at 144'
 Cemented: w/125 sacks

Formation	From	To
Surface soil	0	25
Sand	25	30
Shale	30	450
Shale and shells	450	730
Shale	730	1040
Sand	1040	1130
Shale	1130	1576
Anhydrite	1576	1611
Shale	1611	1840
Shale w/white streaks	1840	1990
Shale w/lime	1990	2135
Lime	2135	2225
Shale and lime	2225	2585
Lime w/shale	2585	2710
Shale w/lime streaks	2710	2910
Shale	2910	3158
Lime	3158	3715
Cherty lime and shale	3715	3744
Siltstone	3744	3755
Artificial	3755	3759 T.D.

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before me

this 3rd day of August, 1962

My commission expires January 3, 1966

TRANSIT CORPORATION

By L. J. Kruse

Paul E. Galt
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 6 1962
 CONSERVATION DIVISION
 Wichita, Kansas