


15-163-02477-00-00
WELL PLUGGING RECORD

STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Biting Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.



Locate well correctly on above
 Section Plat

Rooks _____ County. Sec. 10 Twp. 10 Rge. (E) 19 (W) _____
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$
 Lease Owner. Harbar Drilling Co., et al
 Lease Name. Palmberg Well No. 1
 Office Address. 1019 Central Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole). Rotary dry hole
 Date well completed. 7/31/48 19_____
 Application for plugging filed. 7/31/48 19_____
 Application for plugging approved. 7/31/48 19_____
 Plugging commenced. 8/2/48 19_____
 Plugging completed. 8/2/48 19_____
 Reason for abandonment of well or producing formation. Dry hole
 If a producing well is abandoned, date of last production. None 19_____
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well. Merle Rives
 Producing formation. None Depth to top. _____ Bottom. _____ Total Depth of Well. 3734 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sand & soils	nothing	0	200	10 3/4"	190'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from T.D. to 190'. Set wood plug at 190' and dumped 15 sacks cement on wood plug. Filled surface pipe with heavy rotary mud from to cement to 20 feet of top hole where another wood plug was set and 10 sacks cement was dumped on top plug filling top surface pipe and bottom of cellar.

Note: One drill collar and 5 joints of 1 1/2" drill pipe was left on bottom of hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Harbar Drilling Co.
 Address. 1019 Central Bldg., Wichita, Kansas

08-18-1948

STATE OF Kansas, COUNTY OF Barton, SS.

I, Don S. Packer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) _____

SUBSCRIBED AND SWORN to before me this 17th day of August, 1948

My commission expires Mar. 22, 1952

22-237 7-47-10M

Helen Kelly
 Notary Public.
PLUGGING
 THE SEC 10 T 10 R 19 W
 47 1948

15-163-02477-00-00

PALMBERG #1

SW $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ of Sec. 10-108-19W, Rocks County, Kansas.

Rigging up Rotary Tools 7-18-48
Tearing down Rotary Tools 8-3-48

Run 6 Jts. 19 1/2 feet. 10 3/4" surface casing
Set @ 190 feet and cemented with 100 sx
cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	60
Shale and gravel	60	145
Shale and shells	145	395
Sand and shale	395	450
Shale and shells	450	1000
Sand	1000	1200
Sand and shale	1200	1350
Shale and shells	1350	1500
Red Bed	1500	1610
Shale and shells	1610	2020
Shale	2020	2225
Shale and Lime	2225	2480
Lime	2480	3075
Lime and shale	3075	3215
Lime	3215	3430
Lime and chert	3430	3440
Lime and shale	3440	3480
Lime	3480	3590
Lime and shale	3590	3680
Lime and chert	3680	3696
Lime and shale	3696	3734 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct,
to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 11th day of August, 1948.

William Kelly
Notary Public

My commission expires: Mar. 22, 1952.

