

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Mid-Continent Resources, Inc.

Address: P.O. Box 399

Phone: (785) 398-2270 Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 09/21/2007 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No

Producing Formation(s): List All (if needed attach another sheet)

Mississippian Depth to Top: 4375' Bottom: 4381' T.D. 4393'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-135-23908-00-00

Lease Name: Borger KCC Act 9/28/07 per CP213

Well Number: 3

Spot Location (QQQQ): 70' W of - SE - SW - NW

2310 Feet from [X] North / [] South Section Line

920 Feet from [] East / [X] West Section Line

Sec. 25 Twp. 19 S. R. 22 [] East [X] West

County: Ness

Date Well Completed: 10/02/1995

Plugging Commenced: 09/21/2007

Plugging Completed: 09/21/2007

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Mississippian, Water & Oil, 4375', 4393', 8 5/8", 519, None. Row 2: 5 1/2", 4381', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services pumped 60 sacks of 60/40 poz, 4% gel with 400# of hulls down 5 1/2" casing, followed by 37 barrel water spacer, followed by 160 sacks of 60/40 poz, 4% gel @ vacuum. Let sit for 30 minutes and top off casing with 80 sacks of 60/40 poz, 4% gel, job complete.

Name of Plugging Contractor: Swift Services, Inc License #: 32382

Address: N Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.


State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 210 W Avenue A, Bazine, KS 67516



SUBSCRIBED and SWORN TO before me this 21st day of September, 2007

Bernice Moore Notary Public My Commission Expires: 2/7/10

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 24 2007

CONSERVATION DIVISION