

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior, Inc.  
Address: P.O. Box 399  
Phone: (785) 398 - 2270 Operator License #: 4058  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 09/21/2007 (Date)  
by: Mike Maier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 4379' Bottom: 4399' T.D. 4399'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 135-19011 - 00-00  
Lease Name: Borger  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - NW - NE  
660 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 25 Twp. 19 S. R. 22  East  West  
County: Ness  
Date Well Completed: 09/10/1964  
Plugging Commenced: 09/21/2007  
Plugging Completed: 09/21/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	Water & Oil	4379'	4399'	8 5/8"	409'	None
				5 1/2"	4384'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services pumped 35 sacks of 60/40 poz, 4% gel down 5 1/2" casing, followed by 75 sacks 60/40 poz 4% gel with 200# of hulls @ 700 psi and holding pressure. Pump 45 sacks of 60/40 poz 4% gel down 8 5/8" casing and pressure to 350 psi and held pressure. Job Complete.

Name of Plugging Contractor: Swift Services, Inc License #: 32382  
Address: N Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 210 W Avenue A, Bazine, KS 67516



and SWORN TO before me this 21st day of September 20 07  
Bernice Moore My Commission Expires: 2/17/10  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 24 2007

RECEIVED  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION