

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01371-00-00

API NUMBER 15-7-7-48

LEASE NAME Brault

WELL NUMBER 1

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 14 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 7/7/88

Plugging Commenced 7/1/87

Plugging Completed 7/1/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bowman Oil Company

ADDRESS Box 37 Codell, Ks 67630

PHONE#(913) 434-2304 OPERATORS LICENSE NO. 6931

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/1/87 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3763 Bottom 3767 T.D. 3767

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Water & Oil	3763	3767	5 1/2	3763	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated well at 1450', 975', and 90' and then pumped down 200 sacks of 65/35 poz mix, 10% gel, 2% lite with # flocele and 6 sacks of hulls and cemented well from top to bottom with cement, shut in at 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Kansas 67665

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D. Bowman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Louis D. Bowman

(Address) Box 17, Codell, Ks 67630

SUBSCRIBED AND SWORN TO before me this 24 day of Sept, 19 87

Vesta J. Russell
Notary Public 25 1987

My Commission Expires: July 17, 1988




RECEIVED
STATE CORPORATION COMMISSION
9/25/87 Form CP-4
Revised 07-87

Company **MARBAR DRILLING COMPANY**
 Farm - Brault No. 1

S. 14 T. 9 R. 21W
 SW SE SE

Total Depth: 3765
 Comm. 6-17-48 Comp. 7-7-48
 Shot or Treated.
 Contractor.
 Issued. 4-15-50

County. **Graham**
 KANSAS



CASING:
 10 3/4" 90' cem w/ 45 sx.
 5 1/2" 3763' cem w/100sx.

Elevation. 2258

Production. 8 Bbbls.

Figures Indicate Bottom of Formations.

Surface clay	25
Sand	50
Shale & shells	370
Hard pan	400
Shale & shells	900
Sand	950
Shale & shells	1160
Sandy shale	1300
Sandy shale & shells	1370
Shale, lime, Anhydrite	1405
Shale, Anhydrite	1450
Redbed	1735
Shale & shells	1915
Shale	2010
Lime	2215
Shale & lime	2380
Lime	2465
Lime & shale	3010
Lime	3180
Lime & shale	3285
Lime	3440
Hard lime	3465
Lime	3645
Lime, shale, chert	3620
Cherty conglomerate	3740
Lime	3765
Total Depth	

Perf - 1450' - 4
" - 975' - 3
" - 100' - 3

Tops:

Topeka	3186
Heebner	3412
Toronto	3431
Lansing	3453
B. Pennsylvania Congl.	3706
Simpson	3753
Arbuckle	3763

RECEIVED
 STATE CORPORATION COMMISSION

SEP 25 1987

CONSERVATION DIVISION
 Wichita, Kansas